HASSAN DIVISION.

Notification, dated 7th February 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 3 P.M. on 27th February 1936, for constructing a Lifting Dam across Mosale Tank Valley near Hosahalli, Hassan Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for constructing a Lifting Dam across Mosale Tank Valley, near Hosahalli, Hassan Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate of cost for constructing a Lifting Dam across Mosale tank valley near Hosahalli, Hassan Taluk.

No.	Items of work	Quantity	Per	Rate	Cost
				Rs. a. p.	Rs. a. p.
1	Earthwork excavation for foundation of body wall and returns	543	C.yd.	0 3 6	
2	Stone jelly concrete in surki mortar ..	2,575	C.ft.	0 4 6	
3	Size stone in surki mortar	4,589	,,	0 5 6	
4	Providing and fixing burnt stone slabs of 6" thickness dressed with joggle joints fixed in surki mortar	705	S.ft.	0 8 0	
5	Pointing with cement mortar	9.24	Sqr.	4 0 0	
6	Earthwork to side with watering and tamping, etc., complete, (earth available from excavation)	150	C.yd.	0 1 6	
7	New rough stone work with jelly packing and wedging	433	,,	1 12 0	
8	Providing and fixing regulation arrangement to head sluice with locking arrangements.	Lumpsum	..	..	20 0 0

N. LAKSHMINARASIMHAIYA,
Executive Engineer.